
# WEIGHT ROOM FLOOR REPLACEMENT PACE HIGH SCHOOL

4065 NORRIS ROAD PACE, FL 32571

FOR THE
SANTA ROSA COUNTY SCHOOL BOARD
PHASE II
DOCUMENTS





DRAWING INDEX						
SHEET	OF	SHEET	SHEET #	SHEET NAME		
GENER/	٩L					
1	OF	4	G001	COVER SHEET AND DRAWING INDEX		
STRUCT	ΓURAL					
2	OF	4	S101	EXISTING FOUNDATION AND DEMOLITION PLAN		
3	OF	4	S102	NEW WORK FOUNDATION PLAN		
4	OF	4	S201	STRUCTURAL SECTIONS AND DETAILS		

## OWNER REPRESENTATIVE:

Santa Rosa County School Board Santa Rosa County, Florida Phone: 850-983-5123 Fax: 850-983-5115

Joseph B. Harrell Assistant Superintendent for **Administrative Services** Email: harrelj@mail.santarosa.k12.fl.us

### DESIGN TEAM:

#### STRUCTURAL ENGINEER:

Stephen W. Leonard, PE Berube Leonard, LLC 3101 N 12th Avenue Pensacola, FL 32503

©BERUBE LEONARD, LLC

NOT FOR

CONSTRUCTION

- PRELIMINARY -


- PHASE II REVIEW

STEPHEN W. LEONARD FL PE #60370

Scho Norris Road Florida 32571

PROJECT NO: 08/12/2020 SRCSD SUBMISSION: **REVISIONS:** Description

G001






THE EXISTING 4" CONCRETE SLAB—ON—GRADE INDICATED IS INTENDED FOR DEMOLITION AND REMOVAL. HATCHED AREAS (COLUMNS, WALLS AND FLOOR SLAB) NOTED ON PLAN ARE INTENDED TO REMAIN. ANY DAMAGED TO COLUMNS, WALLS AND SLABS TO REMAIN WILL NEED TO BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

EXISTING SUB—GRADE SOILS SHALL BE EXCAVATED TO A DEPTH OF 12 INCHES BELOW THE BOTTOM OF THE SLAB. THE CONTRACTOR IS RESPONSIBLE TO LOCATE AND PROTECT UNDER—SLAB UTILITIES FROM DAMAGE. SOILS AT THIS LEVEL SHALL BE COMPACTED WITH A MECHANICAL PLATE TAMPER TO A MINIMUM SOIL DENSITY OF 95% OF THE MODIFIED PROCTOR TEST (ASTM D1557). REFER TO GENERAL NOTES ON SHEET S102 FOR ADDITIONAL SOIL PREPARATION INFORMATION.

THE CONTRACTOR IS RESPONSIBLE FOR PROPER DISPOSAL OF DEMOLITION DEBRIS.



©BERUBE LEONARD, LLC

- PRELIMINARY -

NOT FOR

CONSTRUCTION

- PHASE II REVIEW -

STEPHEN W. LEONARD FL PE #60370

1212#00070

RCSD Pace High School Weight Room Floor Replace

Defence:


ace, Florida 32571

ALETTITIE:

XISTING FOUNDATION & DEMOLITION PLAN

PROJECT NO: 20-016  DATE: 08/12/2020  FOR: SRCSD  SUBMISSION:  REVISIONS:  No. Description Date  SHEET		<del>•</del>		
DATE: 08/12/2020  FOR: SRCSD  SUBMISSION:  REVISIONS:  No. Description Date				
FOR: SRCSD  SUBMISSION:  REVISIONS:  No. Description Date	PRC	JECT NO:	20-016	
SUBMISSION:  REVISIONS:  No. Description Date	DAT	E:	08/12/2020	
REVISIONS:  No. Description Date	FOR	:	SRCSD	
No. Description Date	SUB	MISSION:		
	REV	ISIONS:		
SHEET	No.	Description		Date
SHEET				
	Sł	HEET		

S101



#### GENERAL STRUCTURAL NOTES:

1. MATERIALS TO CONFORM TO THE FOLLOWING:

CONCRETE 3,000 PSI AT 28 DAYS
REINF STEEL ASTM A615 GRADE 60
WELDED WIRE FABRIC ASTM A185 (FLAT SHEETS)

EPOXY ADHESIVE RED HEAD G5+ HIGH STRENGTH EPOXY
OR APPROVED EQUIVALENT

2. SUB-GRADE PREPARATION IS IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEERING REPORT PREPARED BY TIERRA, INC. REPORT NO. 4511-20-011 DATED MARCH 31, 2020. REFER TO PROJECT SPECIFICATIONS FOR REPORT.


3. EXISTING SUB—GRADE SOILS SHALL BE EXCAVATED TO A DEPTH OF 12 INCHES BELOW THE BOTTOM OF THE SLAB. SOILS AT THIS LEVEL SHALL BE COMPACTED WITH A MECHANICAL PLATE TAMPER TO A MINIMUM SOIL DENSITY OF 95% OF THE MODIFIED PROCTOR TEST (ASTM D1557).

4. BACKFILL SHALL BE THE EXCAVATED SOILS IN TWO 6—INCH THICK LIFTS EACH COMPACTED TO A MINIMUM SOIL DENSITY OF 95% OF THE MODIFIED PROCTOR TEST (ASTM D1557).

5. ALL ELEVATIONS REFERENCED ON THE STRUCTURAL DRAWINGS ARE ABOVE OR BELOW A FINISHED FLOOR ELEVATION OF  $\pm 0'-0''$ .

6. PLACE REINFORCING IN CONCRETE WITH A MINIMUM OF 3" CLEAR COVER WHEN CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH. PROVIDE CORNER BARS FOR ALL CONTINUOUS HORIZONTAL REINFORCING.

7. FIELD VERIFY ALL EXISTING BUILDING DIMENSIONS SHOWN ON PLANS.



©BERUBE LEONARD, LLC

- PRELIMINARY -

NOT FOR CONSTRUCTION

- PHASE II REVIEW -

STEPHEN W. LEONARD

FL PE #60370

RCSD Pace High School Weight Room Floor Replacement


Obress:
O

П

LION


PROJE	CT NO:	20-016	
DATE:		08/12/2020	
FOR:		SRCSD	
SUBMI	SSION:		
REVIS	IONS:		
No.	Description		Date

S102




TYPICAL SLAB CONTROL JOINT DETAIL

Scale: 3/4' = 1'-0"




TYPICAL SLAB CONSTRUCTION JOINT DETAIL

Scale: 3/4' = 1'-0"



TYPICAL SLAB-ON-GRADE DETAIL

Scale: 3/4' = 1'-0"



TYPICAL REBAR EMBEDMENT TO EXISTING STRUCTURES

Scale: 3/4' = 1'-0"



©BERUBE LEONARD, LLC

- PRELIMINARY 
NOT FOR
CONSTRUCTION

- PHASE II REVIEW -

STEPHEN W. LEONARD FL PE #60370

Weight Room Floor Replacement

Sch

**DETAILS** 

∞

SECTIONS

PROJECT:

SRCSD Pace High S, ADDRESS:

ADDRESS:

ADDRESS:

ADDRESS:

ADGE Norris Road

Pace, Florida 32571

SHEET TITLE:

SHEET TITLE:

STRUCTURAL SEC

**S201**