
WEIGHT ROOM FLOOR REPLACEMENT AT PACE HIGH SCHOOL

4065 NORRIS ROAD
PACE, FL 32571

FOR THE
SANTA ROSA COUNTY SCHOOL BOARD
PHASE III
DOCUMENTS





DRAWING INDEX							
SHEET	OF	SHEET	SHEET #	SHEET NAME			
GENER/	٩L						
1	OF	4	G001	COVER SHEET AND DRAWING INDEX			
STRUCT	ΓURAL						
2	OF	4	S101	EXISTING FOUNDATION AND DEMOLITION PLAN			
3	OF	4	S102	NEW WORK FOUNDATION PLAN			
4	OF	4	S201	INTERIOR ELEVATIONS, SECTIONS AND DETAILS			

OWNER REPRESENTATIVE:

Santa Rosa County School Board Santa Rosa County, Florida Phone: 850-983-5123 Fax: 850-983-5115

Joseph B. Harrell
Assistant Superintendent for
Administrative Services
Email: harrelj@mail.santarosa.k12.fl.us

DESIGN TEAM:

STRUCTURAL ENGINEER:

Stephen W. Leonard, PE Berube Leonard, LLC 3101 N 12th Avenue Pensacola, FL 32503 STRUCTURES

BERUBE LEONARD LLC

3101 NORTH 12TH AVE PENSACOLA, FL 325

850.473.9955 www.BLSE.net EST. 20

FL 9468 | AL CA2463E | GA PEF005473 | MS E01

©BERUBE LEONARD, LLC

- PRELIMINARY - NOT FOR

CONSTRUCTION

- PHASE III REVIEW -

STEPHEN W. LEONARD

FL PE #60370

SRCSD Pace High School Weight Room Floor Replacement

ADDRESS:
4065 Norris Road
Pace, Florida 32571

PROJECT NO: 20-016

DATE: 08/31/2020

FOR: SRCSD


SUBMISSION:

REVISIONS:

No. Description Date


SHEET

GOO1





- 1. REMOVE EXISTING WEIGHT LIFTING EQUIPMENT AND STORE ON SITE FOR REINSTALLATION BY CONTRACTOR. REFER TO EXISTING ELEVATIONS A THROUGH K ON SHEET S201 FOR EQUIPMENT PHOTOS. CONTRACTOR REQUIRED TO PROVIDE SEPARATE LINE ITEM PRICE IN BID FOR ON SITE PORTABLE STORAGE FACILITY.
- 2. REMOVE AND DISCARD EXISTING BASE BOARDS WHERE THE FLOOR SLAB WILL BE REPLACED. REINSTALL NEW BASEBOARDS AFTER PAINTING. REFER TO OWNER DIRECT PURCHASE PROCEDURES AND INTERIOR PAINT AND COATINGS SPECIFICATION SECTIONS.
- 3. REMOVE AND DISCARD EXISTING FLOOR MATS. REINSTALL NEW FLOOR MATS AFTER PAINTING. REFER TO OWNER DIRECT PURCHASE PROCEDURES SPECIFICATION SECTION.
- 4. REMOVE EXISTING WALL HANGINGS AND STORE ON SITE FOR REINSTALLATION.
- 5. DEMOLISH AND DISCARD EXISTING 4"± CONCRETE SLAB—ON—GRADE INDICATED. HATCHED AREAS (COLUMNS, WALLS AND FLOOR SLAB) NOTED ON PLAN ARE INTENDED TO REMAIN. ANY DAMAGED TO COLUMNS, WALLS AND SLABS TO REMAIN WILL NEED TO BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 6. EXCAVATE EXISTING SUB-GRADE SOILS TO A DEPTH OF 12 INCHES BELOW THE BOTTOM OF THE SLAB. STORE EXCAVATED SOILS FOR REUSE. THE CONTRACTOR IS RESPONSIBLE TO LOCATE AND PROTECT UNDER—SLAB UTILITIES FROM DAMAGE. SOILS AT THIS LEVEL SHALL BE COMPACTED WITH A MECHANICAL PLATE TAMPER TO A MINIMUM SOIL DENSITY OF 95% OF THE MODIFIED PROCTOR TEST (ASTM D1557). REFER TO GENERAL NOTES ON SHEET S102 FOR ADDITIONAL SOIL PREPARATION INFORMATION.
- 7. THE CONTRACTOR IS RESPONSIBLE FOR PROPER DISPOSAL OF DISCARDED ITEMS AND DEMOLITION DEBRIS.



©BERUBE LEONARD, LLC

NOT FOR

- PRELIMINARY -

CONSTRUCTION

- PHASE III REVIEW -

STEPHEN W. LEONARD

FL PE #60370

4


EMOLITION

SRCSD Pace High School Weight Room Floor Replacemer 1065 Norris Road 12571

U	∢ `	7	ч	ഗ	ш
PROJECT NO: 20-016					
ΓE:				08/3	1/2020
₹:				SRC	SD
BMISSIO	N:				
/ISIONS	•				
	Descrip	tion		_	Date
				-	
				-	
HEET					
	DJECT N FE: R: BMISSIO	DJECT NO: TE: R: BMISSION: /ISIONS: Descrip	DJECT NO: TE: R: BMISSION: /ISIONS: Description	DJECT NO: TE: R: BMISSION: /ISIONS: Description	DJECT NO: 20- TE: 08/3* R: SRC BMISSION: /ISIONS: Description

S101

 $\frac{EXISTING FOUNDATION & DEMOLITION PLAN}{scale 1/4" = 1'-0"}$



GENERAL NOTES:

1. MATERIALS TO CONFORM TO THE FOLLOWING:

CONCRETE 3,000 PSI AT 28 DAYS
REINFORCING STEEL ASTM A615 GRADE 60
WELDED WIRE FABRIC ASTM A185 (FLAT SHEETS)

EPOXY ADHESIVE RED HEAD G5+ HIGH STRENGTH EPOXY
OR APPROVED EQUIVALENT

2. SUB-GRADE PREPARATION IS IN ACCORDANCE WITH THE GEOTECHNICAL ENGINEERING REPORT PREPARED BY TIERRA, INC. REPORT NO. 4511-20-011 DATED MARCH 31, 2020. REFER TO PROJECT SPECIFICATIONS FOR REPORT.

3. EXISTING SUB—GRADE SOILS SHALL BE EXCAVATED TO A DEPTH OF 12 INCHES BELOW THE BOTTOM OF THE SLAB. SOILS AT THIS LEVEL SHALL BE COMPACTED WITH A MECHANICAL PLATE TAMPER TO A MINIMUM SOIL DENSITY OF 95% OF THE MODIFIED PROCTOR TEST (ASTM D1557).

4. BACKFILL SHALL BE THE EXCAVATED SOILS IN 6—INCH THICK MAXIMUM LIFTS EACH COMPACTED TO A MINIMUM SOIL DENSITY OF 95% OF THE MODIFIED PROCTOR TEST (ASTM D1557). PERFORM 5 TESTS PER LIFT; ONE EACH CORNER AND ONE NEAR THE CENTER.

5. SPRAY FINAL GRADE WITH APPROVED TERMITE TREATMENT.

6. ALL ELEVATIONS REFERENCED ON THE STRUCTURAL DRAWINGS ARE ABOVE OR BELOW A FINISHED FLOOR ELEVATION OF ± 0.00 .

7. FIELD VERIFY ALL EXISTING BUILDING DIMENSIONS SHOWN ON PLANS.

8. PLACE REINFORCING IN CONCRETE WITH A MINIMUM OF 3" CLEAR COVER WHEN CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH. PROVIDE CORNER BARS FOR ALL CONTINUOUS HORIZONTAL REINFORCING.

9. PAINT INTERIOR WALLS IN THE WEIGHT ROOM AREA. MATCH EXISTING SOLID COLORS AND PAINT SCHEME. REFER TO INTERIOR PAINTS AND COATINGS SPECIFICATION SECTION. REPAINTING EXISTING LETTERING AND LOGO ARTWORK NOT REQUIRED.

STRUCTURES

BERUBE LEONARD LLC

3101 NORTH 12TH AVE PENSACOLA, FL 32503
850.473.9955 www.BLSE.net EST. 2003
FL 9468 | AL CA2463E | GA PEF005473 | WS E0143

©BERUBE LEONARD, LLC

- PRELIMINARY -

NOT FOR CONSTRUCTION

- PHASE III REVIEW -


STEPHEN W. LEONARD FL PE #60370

SRCSD Pace High School Weight Room Floor Replacement ADDRESS: 4065 Norris Road Pace, Florida 32571


П

NOI


Ф.			<i>(</i>) <u></u>	
PROJ	ECT NO:		20-016	
DATE	 :	08/31/2020		
FOR:		SRCSD		
SUBM	1ISSION:			
REVIS	SIONS:			
No.	Description		Date	
SH	EET			
	S10	2		




















INTERIOR ELEVATION NOT TO SCALE

INTERIOR ELEVATION NOT TO SCALE








INTERIOR ELEVATION




INTERIOR ELEVATION




INTERIOR ELEVATION




INTERIOR ELEVATION




TYPICAL SLAB CONTROL JOINT DETAIL Scale: 3/4' = 1'-0"




TYPICAL SLAB CONSTRUCTION JOINT DETAIL Scale: 3/4' = 1'-0"



TYPICAL SLAB-ON-GRADE DETAIL



TYPICAL REBAR EMBEDMENT TO EXISTING STRUCTURES



INTERIOR ELEVATIONS - KEY PLAN NOT TO SCALE

ELEVATION Sch Norris Road Florida 32571 Pace High INTERIOR PROJECT: SRCSD 4065
Pace PROJECT NO: 20-016 DATE: 08/31/2020 FOR: SRCSD SUBMISSION: REVISIONS: Description Date

STRUCTURES

BERUBE LEONARD LLC
3101 NORTH 12TH AVE PENSACOLA, FL 32503
850.473.9955 www.BLSE.net EST. 2003
FL 9468 | AL CA2463E | GA PEF005473 | MS E0143

©BERUBE LEONARD, LLC

- PRELIMINARY -

NOT FOR

CONSTRUCTION

- PHASE III REVIEW -

STEPHEN W. LEONARD

FL PE #60370

DETAIL

AND

SECTIONS

eplacement

loor

'eight

SHEET